


Datasheet: 250 - 300kW Loadbank Range

| Description | | | | | | | | |
|--|---------------------|--------------------|-------------------------------------|---|-----------------------|--|--|--|
| Model | | Transp | ortable | Fix | ked | | | |
| Country of Origin | | United Kingdom | | | | | | |
| Max Capacity - Packaged Loadbank | | | 250kW - 300kW | | | | | |
| Voltage Max - Continuous Operation | | 380V - 415V | | | | | | |
| Operating Frequency Range | | | 50Hz | | | | | |
| Phases | | 3ph | | | | | | |
| Wires (Star Connection) | | | 4 | | | | | |
| Load-Step Resolution @ Design Voltage | | | 1kW | | | | | |
| Voltage Tolerance (Short Term Operation) Load Element Tolerance | | | +5% +/-5% | | | | | |
| | | | | | | | | |
| Elements | | 80/20 | 80/20 nickel chrome resistance wire | | | | | |
| nsulation Test | | 80/201 | 500V | | | | | |
| | | 220\/. | 220V - 240V 380V - 415V | | - 415\/ | | | |
| Auxiliary Supply Voltage | | | Hz | | - 415V)Hz | | | |
| Operating Frequency Range | | | | | | | | |
| Phases Load Connections | | 1ph | | 3ph | | | | |
| | | M16 Copper Busbars | | | | | | |
| Protection | | The | Thermal Emergency Cut Out | | | | | |
| Control Voltors | | | Fan Overload | | | | | |
| | | 0.1 | Emergency Stop | | | | | |
| Control Voltage | | | Selectable - Test or Auxiliary | | | | | |
| Cooling Method | | Ford | Forced Air Cooling (Horizontal) | | | | | |
| Air-Flow (Approx.) | | 170m³/min | | | | | | |
| Load Switching Category | | AC-1 Resistive | | | | | | |
| Load Switching Contactor Type | | | 3 Pole AC Contactors | | | | | |
| Rated Maximum Ambient Temperature Operation | | | +40°C / +104°F | | | | | |
| Rated Minimum Ambient Temperature Operation | | | -20°C / -4°F | | | | | |
| Rated Maximum Relative Humidity | | 95% RH | | | | | | |
| Altitude Rating | | <500m [m.a.s.l.] | | | | | | |
| Enclosure | | Sheet Steel | | | | | | |
| Finish | | White - RAL9016 | | | | | | |
| Control Chamber IP Rating | | IP55 | | | | | | |
| _ifting | | Lifting Eyes x2 | | | | | | |
| Enclosure Dimensions | | Castors | Channels | FLB | Fixed | | | |
| Length (Approx.) | mm | 893 | 893 | 893 | 1048 | | | |
| Width (Approx.) | mm | 875 | 875 | 875 | 875 | | | |
| Height (Approx.) | mm | 1325 | 1276 | 1330 | 1276 | | | |
| Total Weight (Approx.) | kg | 260 | 270 | 350 | 275 | | | |
| Loadbank Control Systems | | | | | | | | |
| Control | | K | cs | M | CS | | | |
| | | KCS100H - 10m Lead | | PC Software or HH | | | | |
| Optional Extras: | | VIP - Pov | VIP - Power Meter | | Modbus | | | |
| • | | KCS100 | KCS100L (Local) | | | | | |
| | | KCS100R | , , | | | | | |
| | | | Extendable System Extend - Stand | | Standard | | | |
| | oad Connection Type | | 1-Phase and/or Delta | | | | | |
| Load Connection Type | | | 60Hz and 3-Wire Connection | | | | | |
| Load Connection Type Frequency / Connections | | 601 | 17 and 2-\M | Ire (.annaa | 50m or 100m Extension | | | |
| Frequency / Connections | | | | | | | | |
| Frequency / Connections Control Extension Cables | | 5 | 0m or 100r | m Extensio | n | | | |
| Frequency / Connections Control Extension Cables Transportation | | 5 | 00m or 100r -Wheel Trai | n Extensio iler Mounte | n | | | |
| Frequency / Connections Control Extension Cables Transportation Load Connections | | 5 | 0m or 100r -Wheel Trai Power | m Extension iler Mounte rlocks | n d | | | |
| Frequency / Connections Control Extension Cables Transportation | | 5 | 00m or 100r -Wheel Trai | m Extension iler Mounte rlocks PVC Cover | n d | | | |

250kW - 300kW AC - Issue 1 - 03/02/15 (Changes to specification may vary without notice)







Quality without compromise

Our loadbanks are characterised by one thing above all: quality. At every stage of our supply chain, from raw material to finished item, we work with established, worldclass suppliers and implement our own uncompromising quality control processes to ensure that our products perform better and last longer.

Note: Loadbank illustrated with rental crash pack option





FRONT VIEW

For further information contact:

Crestchic Limited Second Avenue, Centrum 100 Burton-on-Trent, DE14 2WF United Kingdom Tel +44 (0) 1283 531645 Fax +44 (0) 1283 510103 sales@crestchic.co.uk hires@crestchic.co.uk www.crestchic.co.uk The information given in this literature is, to the best of our knowledge, correct at the time of going to print. However, Crestchic is constantly looking at ways of improving their products and services and therefore reserve the right to change, without prior notice, any of the data contained in this publication. Any orders placed will be subject to our Standard Conditions of Sale, available on request. Crestchic is part of the NBI group of companies.



